

No: IITMandi(CW)/SE-856/2017-18/354-55

Date: 27-06-2017

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned so as to reach in this office on or before 04-07-2017 up to 03:00 PM and shall be opened on the same day at 03:30 PM in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractor or their authorized representatives.

Name of work: Leveling of volley ball court and construction of walk path in north campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for Civil works amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed within 10 days from issue of work.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Dean (I& S)

COPY TO:-

1. IIT Mandi website.
2. Notice Board.

Sd/-
Dean (I &S)

SCHEDULE OF QUANTITY

Name of work:- Levelling of volley ball court and construction of walk path in north campus of IIT Mandi

Sr. No.	Description of items	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge:All kinds of soil as per entire satisfaction and direction of Engineer-in-charge	3654.00	sqm			
2	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared as per entire satisfaction and direction of Engineer-in-charge	1600.00	sqm			
Total						

Sd/-
Dean (I&S)