

No: IITMandi(CW)/SE-868 /2017-18/504-05

Date:17.07.2017

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned so as to reach in this office on or before 31.07.2017 up to 03:00 PM and shall be opened on the same day at 03:30 PM in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractor or their authorized representatives.

Name of work: Construction of Toe wall behind Gharpa Guest House of IIT MANDI KAMAND.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for Civil works amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed within 20 days from issue of work.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

- COPY TO:-
1. IIT Mandi website.
 2. Notice Board.

Sd/-
Superintending Engineer

SCHEDULE OF QUANTITY

| Name of work : - Construction of Toe wall behind Gharpa Guest House of IIT MANDI KAMAND. | | | | | |
|---|---|-------|------|-------------|-----------|
| Sr. No. | Description of items | Qty. | Unit | Rate(In Rs) | |
| | | | | (In Figure) | (In Word) |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil. as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all lead and lift. | 35.00 | cum | | |
| 2 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all lead and lift. | 8.15 | cum | | |
| 3 | Coursed rubble masonry (second sort) with hard stone in foundation & plinth with : Cement mortar 1:6 (1 cement : 6 coarse sand) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all lead and lift. | 53.00 | cum | | |
| 4 | Hard Boulder stone for backfilling Hand Picked behind Retaining wall including carriage of material with in all lead and lift as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all lead and lift. | 16.00 | cum | | |
| Total | | | | | |

Sd/-
Superintending Engineer