

No: IITMandi(CW)/SE-870 /2017-18/561-62

Date:25.07.2017

### NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors of appropriate class so as to reach in this office on or before 31-07-2017 up to 03:00 PM and shall be opened on the same day at 03:30 PM in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractor or their authorized representatives.

Name of work: Providing & fixing 1No of Modular Kitchen for existing Guest house Gharpa at South Campus of IIT Mandi.

----- As Per Schedule Attached -----

#### Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for Civil works amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **15 days** from issue of work.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-  
Superintending Engineer

#### COPY TO:-

1. IIT Mandi website.
2. Notice Board.

Sd/-  
Superintending Engineer

### Schedule of Quantity

**Name of Work : - Providing and fixing 1 no. of modular kitchen for Existing Guest House Gharpa at South Campus of IIT Mandi.**

Sr. No.	Description of items	Qty.	Unit	Rate (In Rs)	Amount (In Rs)
1	Providing and fixing of cabinet accessories i.e. Detergent Holder (Home Care/Sleek/Ebco) (Size as per drawing attached) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1	Each		
2	Providing and fixing of cabinet accessories i.e. Cutlery Perforated (Home Care/Sleek/Ebco) (Size as per drawing attached) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1	Each		
3	Providing and fixing of cabinet accessories i.e. Plain Basket (Home Care/Sleek/Ebco) (Size as per drawing attached) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	3	Each		
4	Providing and fixing of cabinet accessories i.e. Plain Basket (Home Care/Sleek/Ebco) (Size as per drawing attached) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1	Each		
5	Providing and fixing of cabinet accessories i.e. Grain Trolley (Home Care/Sleek/Ebco) (Size as per drawing attached) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	2	Each		
6	Providing and fixing of cabinet accessories i.e. Cylinder Trolley (Home Care/Sleek/Ebco) as per entire satisfaction and	1	Each		

	direction of Engineer-in-charge including carriage of material in all leads and lifts.				
7	Providing and fixing of cabinet accessories i.e. GT+PT Tray (Home Care/Sleek/Ebco) (Size as per drawing attached) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1	Each		
8	Providing and fixing of cabinet accessories i.e. Drip Tray (Home Care/Sleek/Ebco) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1	Each		
9	Providing and fixing of cabinet accessories i.e. Bottle Pullout (Home Care/Sleek/Ebco) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1	Each		
10	Providing and fixing of cabinet accessories i.e. Channels (Home Care/Sleek/Ebco) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	8	Set		
11	Providing and fixing Electrical Chimney air suction capacity 700-900 M3/hr (Glen GL 6052 SS or Faber HeatKraft CLEO 700 LTW SS D or KAFF Ray 60) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1	Each		
12	Providing and fixing of Kitchen lower cabinets (as per drawing for one no. kitchen, cabinets are to be provided as per drawing attached and as shown in the drawing) including all fittings as mentioned below complete in all respect as per the direction of engineer -in-charge. Cabinets should be made of 18mm/19mm board	1	Each		

	(decorative finish) Greenlam or Action or centuryply (waterproof and termite proof) Fitting Material i.e. Shutter Hinges, Rastex, Dowel, Sockets, shelf support etc. of Hettich or Ebco make Edge Bands of Rehau Make or equivalent (Size and length of cabinet is as per drawing attached for 1 no. kitchen) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.				
13	Providing and fixing of Kitchen Upper cabinets (as per drawing for one no. kitchen, cabinets are to be provided as per drawing attached and as shown in the drawing) including all fittings as mentioned below complete in all respect as per the direction of Engineer-in-charge. Cabinets should be made of 18mm /19mm board Greenlam or Action or centuryply (waterproof and termite proof) (decorative finish) Fitting Material i.e. Shutter Hinges, Rastex, Dowel, Sockets, Shelf support etc. of Hettich or Ebco make Edge Bands of Rehau Make equivalent (Size and length of cabinet is as per drawing attached for 1 no. kitchen) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1	Each		
Total					

Sd/-  
Superintending Engineer