

No: IIT Mandi (CW)/SE- 965/2018-19/5944-45

Date: 20-09-2018

NOTICE INVITING QUOTATION

Quotation for the work "Providing and laying of tile flooring, demolishing of existing foundation platform and filling of cable trench in UV lab at Kamand Campus of IIT Mandi." as per schedule attached is hereby invited by the undersigned from registered contractors of appropriate class which shall be handed over to members of works/purchase committee on or before **25-09-2018 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed within **15 days** from issue of work order.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
9. GST Registration Certificate should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

Copy To:-

1. Notice board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of work:- Providing and laying of tile flooring, demolishing of existing foundation platform and filling of cable trench in UV lab at Kamand Campus of IIT Mandi.

Sr. No.	Description of Item	Qty.	Unit	Rate (In Rs)		Amount (In Rs)
				(In Figure)	(In Words)	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) as per entire satisfaction and direction of Engineer-in-charge.	0.80	cum			
2	Extra for cutting reinforcement bars manually/ by mechanical means in R.C.C. or R.B. work (Payment shall be made on the cross sectional area of R.C.C. or R.B. work) as per entire satisfaction and direction of Engineer-in-charge.	5.20	sqm			
3	Providing and laying hard stone for soling hand packed under floor i.e carriage of material with in lead and lift as per entire satisfaction and direction of Engineer-in-charge.	2.50	cum			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size) as per entire satisfaction and direction of Engineer-in-charge.	1.30	cum			
5	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm as per entire satisfaction and direction of Engineer-in-charge.	59.50	sqm			
6	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm as per entire satisfaction and direction of Engineer-in-charge.	3.35	sqm			
Total						

Note :- 1.Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer