

No:-IIT Mandi (CW)/SE-968/2018-19/1514-15

Dated: 08/05/2018

**NOTICE INVITING QUOTATION**

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from Registered Contractors so as to reach in this office on or before **14/05/2018 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractor or their authorized representatives.

Name of work: **Providing additional points in Faculty Cabin in A-8 Building South Campus of IIT Mandi.**

----- As Per Schedule Attached -----

**Terms & Conditions:-**

1. The work will be carried out as per CPWD General Specifications for **Electrical works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed within **15 days** from issue of work.
3. All damages done during execution of the work is to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Agency shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. Certificate of Registration should also be attached with NIQ.
9. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-

Superintending Engineer

COPY TO:-

1. Notice Board.
2. Institute Website.

Sd/-

Superintending Engineer

**Schedule of Quantity**

**Name of Work :- Providing additional points in Faculty Cabin in A-8 Building South Campus of IIT Mandi.**

Sr. No.	Item Description	Qty	Unit	Rates (In Rs)		Amount (INR)
				(In Figure)	(In Words)	
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed heavy duty PVC casing, with modular switch, modular plate, suitable PVC box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required of make:- Havells, KEI, Finolex as per entire satisfaction and direction of engineer-in-charge.	40	Point			
2	Wiring for circuit/ submain wiring along with earth wire with the 2 x 2.5 Sq. mm. + 1 x 2.5 Sq. mm of FRLS PVC insulated copper conductor, single core cable in surface/ recessed heavy duty PVC casing as required of make:- Havells, KEI, Finolex as per entire satisfaction and direction of engineer-in-charge.	85	Metre			
3	Supplying and drawing 3 x 2.5 Sq. mm FRLS PVC insulated copper conductor single core cable in existing surface / recessed heavy duty PVC casing as required of make:- Havells, KEI, Finolex as per entire satisfaction and direction of engineer-in-charge.	55	Metre			
4	Supplying and drawing 6 x 2.5 Sq. mm. FRLS PVC insulated copper conductor single core cable in existing surface / recessed heavy duty PVC casing as required of make:- Havells, KEI, Finolex as per entire satisfaction and direction of engineer-in-charge.	15	Metre			
5	Supplying and drawing 9 x 2.5 Sq. mm FRLS PVC insulated copper conductor single core cable in existing surface / recessed heavy duty PVC casing as required of make:- Havells, KEI, Finolex. as per entire satisfaction and direction of engineer-in-charge.	12	Metre			

Sr. No.	Item Description	Qty	Unit	Rates (In Rs)		Amount (INR)
				(In Figure)	(In Words)	
6	Supplying and drawing 3 x 6 Sq. mm FRLS PVC insulated copper conductor single core cable in existing surface / recessed heavy duty PVC casing as required of make:- Havells, KEI, Finolex as per entire satisfaction and direction of engineer-in-charge.	4	Metre			
7	Supplying and fixing 5/6 amp switch modular on the existing modular plate & switch box including connections but excluding modular plate etc. as required of make :- Havells Crabtree Athena, Northwest, Philips as per entire satisfaction and direction of engineer-in-charge.	20	Each			
8	Supplying and fixing 3 pin 5/6 amp socket outlet modular on the existing modular plate & switch box including connections but excluding modular plate etc. as required of make :- Havells Crabtree Athena, Northwest, Philips as per entire satisfaction and direction of engineer-in-charge.	20	Each			
9	Supplying and fixing 15/16 amp switch modular on the existing modular plate & switch box including connections but excluding modular plate etc. as required of make :- Havells Crabtree Athena, Northwest, Philips as per entire satisfaction and direction of engineer-in-charge.	3	Each			
10	Supplying and fixing 6 pin 15/16 amp socket outlet modular on the existing modular plate & switch box including connections but excluding modular plate etc. as required of make :- Havells Crabtree Athena, Northwest, Philips as per entire satisfaction and direction of engineer-in-charge.	3	Each			
11	Supplying and fixing 3 Module , PVC box alongwith modular base & cover plate for modular switches in recess etc as required of make :- Havells Crabtree Athena, Northwest, Philips as per entire satisfaction and direction of engineer-in-charge.	3	Each			
12	Supplying and fixing 6 Module , PVC box alongwith modular base & cover plate for modular switches in recess etc as required of make :- Havells Crabtree Athena, Northwest, Philips as per entire satisfaction and direction of engineer-in-charge.	10	Each			

Sr. No.	Item Description	Qty	Unit	Rates (In Rs)		Amount (INR)
				(In Figure)	(In Words)	
13	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of Single pole, in the existing MCB DB complete with connections, testing and commissioning etc. as required of make:- Havells, C&S, L&T, Hager as per entire satisfaction and direction of engineer-in-charge.	15	Each			
14	Supplying and fixing 63 Amp, double pole, 240 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required of make:- Havells, C&S, L&T, Hager as per entire satisfaction and direction of engineer-in-charge.	2	Each			
15	Supplying and fixing 12 way, Double door, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) of make:- Havells, C&S, L&T, Hager as per entire satisfaction and direction of engineer-in-charge.	2	Each			
16	Supplying and fixing of Heavy duty 32 mm PVC casing capping double lock along with accessories in surface as required of make :- Diplast, Polyfit, AKG as per entire satisfaction and direction of engineer-in-charge.	70	Metre			
17	Supplying, installation, testing and commissioning of decorative ultra slim LED lighting fixture with co extruded polycarbonate body, environmental friendly, energy efficient 20 watt LED 6500K luminaries of make:- Havells, Wipro, Philips as per entire satisfaction and direction of engineer-in-charge.	10	Each			
18	Supplying, installation, testing and commissioning of Wall Fan 400 mm sweep complete with connecting wires etc. as required of make:- Havells, Bajaj, Usha as per entire satisfaction and direction of engineer-in-charge.	10	Each			

Sr. No.	Item Description	Qty	Unit	Rates (In Rs)		Amount (INR)
				(In Figure)	(In Words)	
19	Supply, installation, testing & commissioning of Exhaust fan 250 mm sweep complete with required mounting bracket, of required size and length , connecting wires etc. of make:- Havells, Bajaj, Usha as per entire satisfaction and direction of engineer-in-charge.	10	Each			
	<b>Total</b>					

Note :- 1.Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

sd/-  
Superintending Engineer