

### NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **10/07/2023 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Name of work: - **Supplying and Fixing Power Points in CVO Office at A9 Block in North Campus of IIT Mandi.**

----- As Per Schedule Attached -----

#### Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Electrical works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **20 days** from issue of work order.
3. All damages done during execution of the work is to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge

Sd/-  
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-  
Superintending Engineer

### Schedule of Quantity

**Name of Work:- Supplying and Fixing Power Points in CVO Office at A9 Block in North Campus of IIT Mandi.**

Item no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Supplying and drawing 3x4 sq mm of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/ PVC conduit/Casing/Wall Trunk as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	260.00	Meter			
2	Supplying and fixing of 25 mm of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	20.00	Meter			
3	Supplying and fixing 5/6 A switch modular switch on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	12.00	Each			
4	Supplying and fixing 15/16 A switch modular switch on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	3.00	Each			
5	Supplying and fixing 3 pin 5/6 A socket outlet modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	12.00	Each			
6	Supplying and fixing 6 pin 15/16 A socket outlet modular socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	3.00	Each			
7	Supplying and fixing 3 Module Modular base & cover plate on existing modular metal boxes etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	7.00	Each			
8	Supplying and fixing 6 Module Modular base & cover plate on existing modular metal boxes etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	4.00	Each			
9	Supplying and fixing Single pole 5 to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of Single pole, in the existing MCB DB complete with connections, testing and commissioning etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	3.00	Each			
10	Supplying and fixing 3 Module PVC box to be fixed on Recess or in Open Surface as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	7.00	Each			
11	Supplying and fixing 6 Module PVC box to be fixed on Recess or in Open Surface as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	4.00	Each			

12	Supplying and fixing of 50 X 16 mm size of medium class PVC Casing-Capping along with accessories in surface as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts. and fixing of 50 mm size of medium class PVC Casing-Capping along with accessories in surface as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	26.00	Meter			
13	Supplying and fixing of 32 X 12 mm size of medium class PVC mini trunking along with accessories including coupler, tee, elbow, internal bend, external bend etc. in surface as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	50.00	Meter			
14	Supplying and Installation of wall fan with sweep 300 mm , air delivery 34 m <sup>3</sup> /min and 1280 rpm in white colour as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	4.00	Each			
<b>Total</b>						

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).  
2. All Statutory deduction will be made as per prevailing rates.

Sd/-  
Superintending Engineer