

No: IIT Mandi (CW)/SE- 947/2019-20/2521-22

Date: 01/06/2019

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **07/06/2019** up to **03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives

Name of work:- Providing and fixing 6 no's Wardrobe for Faculty Quarter at South Campus (Gharpa) of IIT Mandi.

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed within **30 days** from issue of work order.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. All material to be used on the work will have to be got approved from the Engineer-in-charge

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of work : -Providing and fixing 6 no's Wardrobe for Faculty Quarter at South campus(Gharpa) of IIT Mandi

| Sr. No. | Description of items | Qty. | Unit | Rate(In Rs) | | Amount (In Rs) |
|---------|---|------|------|-------------|-----------|-------------------|
| | | | | (In Figure) | (In Word) | |
| 1 | Wardrobe (900X600X2100mm) made of 18/19 mm medium density fibre/particle board (Action tea/Greenlam/Century Ply) with shelves making one large size compartment,hanging rod for hanging clothes and other equal compartments of standard size. The unit having lockable doors made of medium density fibre/particle board (Action tesa/Greenlam/ Century Ply) fitted with snap on special hinges of Hettich make with mounting plates. The wardrobe provided with 150mm SS handles. All panels of unit are inter connected with rastex, dowel,sockets and brackets of Hettich make. All the exposed edges of board provided with machine pressed 0.8mm thick PVC edge bands glued with hot melt EVA glue as per drawing attached and entire satisfaction of Engineer-in-charge. | 6.00 | Each | | | |
| | TOTAL | | | | | |

- Note :-
1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).
 2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer