

INDIAN INSTITUTE OF TECHNOLOGY MANDI (HP)

No.IIT Mandi/OSD-1029/Hort./ 2019-20/13069-75

Dated: 08/01/2020

NOTICE INVITING QUOTATIONS

Sealed item rate quotations are hereby invited from individual/firms/agencies for the below noted work up to 17/01/2020 (3.00 P.M.) and shall be opened on the same day at 3.30 P.M.

NAME OF WORK:- Providing and laying drip /sprinkler irrigation system (popup System) for village square Lawn at North Campus IIT Mandi(HP)

Sr.No.	Item	Quantity	Rate	Amount
1	As per schedule attached			

Terms and conditions:-

- (1)The rates should be inclusive of all taxes such as GST or any other taxes and cartage etc.. Nothing Extra will be payable on any account.
- (2) The Time allowed to carry out the work is 15 days.
- (3)The agency is to quote the rates in figures as well as in words.
- (4) The work is to be carried out as per the direction of JE (Hort.)
- (5) Necessary recoveries such as income tax etc. will be deducted from the bill.

Sd/-
Officer on Special Duty
IIT Mandi(HP)

Copy To:-

1. Dr. Rahul Vaish, Chairman, Purchase Committee , IIT Mandi for information Please.
2. Dr. Shyamasree Dasgupta, Member, Purchase Committee , IIT Mandi for information Please.
3. Dr. C.S.Yadav, Member, Purchase Committee , IIT Mandi for information Please.
4. Ms. Lishma Anand ,Member, Purchase Committee , IIT Mandi for information Please.
5. Notice Board IIT Mandi
6. Institute website.
7. JE(Hort), IIT Mandi(HP)

Sd/-
Officer on special Duty

Schedule of Quantity

Name of work:- Providing and laying Drip/sprinkler irrigation system (pop up system) for village square lawn at North Campus, IIT Mandi(HP)

S.No.	Item	Qty	Unit	Rate in		Amount
				Figure	Words	
1	Supply of following items at north campus, IIT including cartage and GST etc.					
	(i) PVC pipe @6kg/sqcm, 63mm size	198	Metre			
	(ii) PVC control valve ,63mm	3	Each			
	(iii) PVC flush Valve,63mm	3	Each			
	(iv) Disc Clean filter@ 20M3/hr,50mm	1	Each			
	(v) Pop up (Pop star plus) ,20mm(3/4 inches)	17	Each			
	(vi) Drip 3/4 inch X30cm,swing joint , male connector	17	Each			
	(vii) PVC ARV 32mm, male SU	1	Each			
	(viii) PG2 with PG adaptor1/4 female thread, 25mm size	1	Each			
	(ix) PVC service saddle 63x 32mm	2	Each			
	(x) PVC service saddle 63x 25mm	19	Each			
	(xi) Drip line R 16mm,2.0LPH 30cm, CL2,100m of size 16mm	200	Metre			
	(xii) Male thread adaptor 63mm-HD	5	Each			
	(xiii) Feale thread adaptor 63mm-HD	5	Each			
	(xiv)PVC elbow 63mm	12	Each			
	(xv) PVC equal Tee63mm	4	Each			
2	Laying PVC pipe including fixing of pops, jointing of all fittings with PVC solvent, including testing of joints complete as per the direction of Engineer-in-charge but excluding trenching and refilling. (a) External work					
	(i) 16mm dia pipe	200	Metre			
	(ii) 63mm dia pipe	198	Metre			
Note:- (i) The above rates should be inclusive of GST as well as labour cess and nothing extra is payable on any account such as cartage etc.						

Sd/-

JE(Hort)

IIT Mandi (HP)

Sd/-

Officer on Special Duty

IIT Mandi(HP)