

INDIAN INSTITUTE OF TECHNOLOGY MANDI (HP)

No.IIT Mandi/OSD-1029/2019-20/3640-47

Dated: 25 / 06 / 2019

NOTICE INVITING QUOTATIONS

Sealed item rate quotations are hereby invited from individual/firms/agencies for the below noted work up to 03/07/2019 (3.00 P.M.) and shall be opened on the same day at 3.30 P.M.

NAME OF WORK:- Development of Fish pond area near A-7 building at South Campus by raising the surface.

Sr.No.	Item	Quantity	Rate	Amount
1	As per schedule attached			

Terms and conditions:-

- (1)The rates should be inclusive of all taxes such as GST or any other tax. Nothing Extra will be payable on any account.
- (2) The work is to be carried out within 15 days of issue of work order.
- (3)The agency is to quote the rates in figures as well as in words.

Sd/-
Officer on Special Duty
IIT Mandi(HP)

Copy To:-

1. Dr. C.S. Yadav, Chair, Purchase Committee, IIT Mandi for information Please.
2. Dr.Sandip Kumar Saha, Member, Purchase Committee, IIT Mandi for information Please.
3. Er. Sunil Kapoor, Member, Purchase Committee, IIT Mandi for information Please.
4. Er. Amar Singh ,Member, Purchase Committee,IIT Mandi for information Please
5. Sh. Parminder Jit Gill,Member, Purchase Committee, IIT Mandi for information Please
6. Interested Agencies
7. Notice Board IIT Mandi
8. Institute website.

Sd/-
Officer on special Duty
IIT Mandi (HP)

SCHEDULE OF QUANTITY

Name of work:- Development of Fish pond area near A-7 building at South Campus by raising the surface

S.No.	Item	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Brick work with class designation 75 in cement mortar 1:6(1 Cement : 6 Coarse sand) in foundation and plinth	2.00	Cum			
2	12 mm Cement plaster in cement mortar 1:6(1 Cement : 6 Coarse sand)	9.00	Sqm			
3	Providing Kota stone slab coping over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) using single length of kota stone up to 1.05 metre.	8.40	Sqm			
4	Supply of fine sand at site	10.00	Cum			
5	Cutting holes in CC pavement of 60cm dia upto ground by means of drilling machines as per the direction of Engineer-in-charge	8	Each			
	Total					

Sd/-
Officer on Special Duty