



No: IIT Mandi (CW)SE-1077/2019-20/10960-61

Date: 25/11/2019

## NOTICE INVITING QUOTATION

Quotation for the work "Improving the drainage system of CV Raman canteen & IC Engine lab and laying of C.C Flooring in Main Gate Security Post at South Campus of IIT Mandi." as per schedule attached is hereby invited by the undersigned from registered contractors which shall be handed over to members of works/purchase committee on or before **02/12/2019 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Construction Wing, IIT Mandi at Kamand campus in the presence of intending contractor or their authorized representatives.

### Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed within **30 days** from issue of work order.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-  
Superintending Engineer

Copy To:-

1. Notice board.
2. Institute Website.

Sd/-  
Superintending Engineer

## Schedule of Quantity

**Name of work :** -Improving the drainage system of CV Raman canteen & IC Engine lab and laying of C.C Flooring in Main Gate Security Post at South Campus of IIT Mandi.

Sr. No.	Description of items	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figures)	(In Word)	
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil as per direction of Engineer - in - charge.	11.90	sqm			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size as per entire satisfaction and direction of Engineer -in-charge including carriage of material in all lead and lift.	9.21	cum			
3	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete as per entire satisfaction and direction of Engineer -in-charge including carriage of material in all lead and lift.	1.72	sqm			
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand) as per entire satisfaction and direction of Engineer -in-charge including carriage of material in all lead and lift.	1.20	cum			
5	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix) as per entire satisfaction and direction of Engineer -in-charge including carriage of material in all lead and lift.	0.92	cum			
6	Providing and laying n NP2 class (light duty) R.C.C. pipes half cut for open Drain 300 mm dia. Half cut R.C.C. pipe as per entire satisfaction and direction of Engineer -in-charge including carriage of material in all lead and lift.	66.00	mtrs			

Note :-  
 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).  
 2. All Statutory deduction will be made as per prevailing rates.

Sd/-  
 Superintending Engineer