

No: IIT Mandi(CW)/SE-1094/2019-20/15316-317

Date:04-03-2020

NOTICE INVITING QUOTATION

Quotations for the work "Electrical Wiring for new proposed scholar sitting space at A-13 Block, North Campus of IIT Mandi." as per schedule attached is hereby invited by the undersigned from registered contractors/ firms upto 12-03-2020 by 03:00 PM and shall be opened on the same day at 03:30 PM in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractor or their authorized representatives.

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Electrical works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed immediately within **20 days** after issue of work order.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra shall be paid on this account.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. Compensation of delay of work will @ 0.05% per day on account of non-completion of work within stipulated period.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge/faculty.

Sd/-
Superintending Engineer

COPY TO:-

1. Notice board.
2. Institute website

Sd/-
Superintending Engineer

Schedule of Quantity

Name Of Work:- Electrical Wiring for new proposed scholar sitting space at A-13 Block, North Campus of IIT Mandi.

Sr. No.	Description	Qty.	Unit	Rate (In Rs)		Amount (In Rs)
				(In Figure)	(In words)	
1	Supplying the 4 Core 6 mm sq. Unarmoured Copper cable.	55	Metre			
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel / PVC conduit as required.					
(i)	3 X 4 sq. mm	200	Metre			
3	Supplying and fixing of 25 mm of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.	100	Metre			
4	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
(i)	5/6 amps switch	60	Each			
(ii)	15/16 amp switch	6	Each			
(iii)	3 pin 5/6 amp socket outlet	60	Each			
(iv)	6 pin 15/16 amp socket outlet	6	Each			
5	Supplying and fixing following size/ modules, PVC box alongwith modular base & cover plate for modular switches in recess etc as required.					
(i)	3 Module (100mmX75mm)	6	Each			
(ii)	6 Module (200mmX75mm)	30	Each			
6	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/DCCB/Isolator)					
(i)	6 way (4 + 18), Double door	1	Each			
7	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
(i)	Single pole	18	Each			
8	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
(i)	63 amps	1	Each			
9	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required.					
(i)	Upto 35 sq. mm (clamped with 1mm thick saddle)	55	meter			
Total						

Note:-

1. Quoted rate should be inclusive of all applicable taxes including GST (nothing extra shall be payable).
2. All Statutory deduction will be made as per prevailing rates.

**Sd/-
Superintending Engineer**