



No. IITMandi(CW)/SE-1481/2023-24/4163-64

Dated:10/10/2023

**NOTICE INVITING QUOTATION**

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **18/10/2023 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand South campus in the presence of intending contractors or their authorized representatives.

**Name of Work: Providing and fixing Power points in SBB labs at A1 and A6 top floors at South Campus of IIT Mandi.**

----- As Per Schedule Attached -----

**Terms & Conditions:-**

1. The work will be carried out as per CPWD General Specifications for **Electrical works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **20 days** from issue of work order.
3. All damages done during execution of the work is to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge

Sd/-  
Assistant Engineer (E)

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-  
Assistant Engineer (E)

### Schedule of Quantity

**Name of Work:- Providing and fixing Power points in SBB labs at A1 and A6 top floors at South Campus of IIT Mandi.**

Item no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Supplying and drawing 3x4 sq mm of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/ PVC conduit/Casing/Wall Trunk as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	190.00	Meter			
2	Supplying and fixing of 32 sq mm of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	50.00	Meter			
3	Supplying and fixing 5/6 A switch modular switch on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	6.00	Each			
4	Supplying and fixing 15/16 A switch modular switch on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	19.00	Each			
5	Supplying and fixing 3 pin 5/6 A socket outlet modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	6.00	Each			
6	Supplying and fixing 6 pin 15/16 A socket outlet modular socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	19.00	Each			
7	Supplying and fixing 3 Module Modular base & cover plate on existing modular metal boxes etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	6.00	Each			
8	Supplying and fixing 6 Module Modular base & cover plate on existing modular metal boxes etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	8.00	Each			
9	Supplying and fixing 8 Module Modular base & cover plate on existing modular metal boxes etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1.00	Each			

10	Supplying and fixing 12 way Double door, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1.00	Each		
11	Supplying and fixing Single pole 5 to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of Single pole, in the existing MCB DB complete with connections, testing and commissioning etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	10.00	Each		
12	Supplying and fixing 63A rating, double pole, 240 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1.00	Each		
13	Supplying and fixing 3 Module PVC box in open surface/wall as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	6.00	Each		
14	Supplying and fixing 6 Module PVC box in open surface/wall as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	8.00	Each		
15	Supplying and fixing 8 Module PVC box in open surface/wall as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1.00	Each		
16	Supplying and drawing 3x10 sq mm of FR PVC insulated copper conductor, single core cable in the existing surface/recessed steel/ PVC conduit as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	5.00	Meter		
17	Supplying and fixing of 32 mm size of Heavy Duty PVC Casing Caping Double lock along with accessories in surface as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	50.00	Meter		
<b>Total</b>					

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).  
2. All Statutory deduction will be made as per prevailing rates.

Sd/-  
Assistant Engineer(Elect.)