

IITMandi(CW)/SE-1142/2020-21/6091-92

Dated:16/02/2021

**NOTICE INVITING QUOTATION**

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **19/02/2021 up to 11:00 AM** and shall be opened on the same day at **11:30 AM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Name of work: - **Re- painting over toe walls and retaining walls along the RCC road from A-09 to A-16 and re-painting b/s of A-08 auditorium block along the RCC road and b/s of A-07 medical unit block along the RCC road at North campus of IIT Mandi.**

----- As Per Schedule Attached -----

**Terms & Conditions:-**

1. The work will be carried out as per CPWD General Specifications for **Civil work** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **04 days** from issue of work order.
3. All damages done during execution of the work is to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Agency shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge

Sd/-  
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-  
Superintending Engineer

## Schedule of Quantity

**Name of Work:-** Re- painting over toe walls and retaining walls along the RCC road from A-09 to A-16 and re-painting b/s of A-08 auditorium block along the RCC road and b/s of A-07 medical unit block along the RCC road at North campus of IIT Mandi.

Sr. No.	Description of items	Qty.	Unit	Rate( in Rs)		Amount (in Rs)
				(in Figures)	(in Word)	
1	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work as per entire satisfaction and direction of Engineer in charge.	525.00	sqm			
2	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm)over priming coat of primer applied @ 0.80 liters/10 sqm complete including cost of Priming coat as per entire satisfaction and direction of Engineer in charge.	560.00	sqm			

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-  
Superintending Engineer