

No. IITMandi(CW)/SE-1192/2021-22/3834-35

Dated:08/11/2021

**NOTICE INVITING QUOTATION**

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **15/11/2021 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

**Name of work: Providing mineral fibre false ceiling at A3 top floor South Campus of IIT Mandi.**

----- As Per Schedule Attached -----

**Terms & Conditions:-**

1. The work will be carried out as per CPWD General Specifications for **Civil works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **30 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Contractor shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-  
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-  
Superintending Engineer

## Schedule of Quantity

Name of Work:-providing mineral fibre false ceiling at A3 top floor South Campus of IIT Mandi.

Sr.no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	<p>Providing and Fixing tiles of size 595 x 595 mm in true horizontal level suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38mm made from 0.33 mm thick (minimum) sheet, spaced 1200mm centre to centre, and cross "T" of size 24x28mm made out of 0.33mm (Minimum) sheet, 1200mm long spaced between main'T' at 600mm centre to centre to form a grid of 1200x600mm and secondary cross 'T' of length 600mm and size 24 x28mm made of 0.33mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600mm panel to from grid of size 600x600mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450mm centre to centre with 25mm long dry wall screws @ 230mm interval and laying the tiles in the grid including, cutting/ making opening for services like diffusers, grills,light fittings, fixtures, smoke detectors etc., wherever required, Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6mm fixed to ceiling with 12.5 mm dia and 50mm long dash fasteners, 4mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200mm centre to centre along main 'T' , bottom exposed with 24mm of all T-sections shall be pre-painted with polyster baked paint, for all heights, as per specifications, drawings and as directed by engineer-in-charge.</p> <p>Note :- Only tiled false ceiling area will be measured from wall to wall. No deduction shall be made for exposed frames/opening (cut outs) having area less than 0.40 sqm.</p> <p>12mm thick Mineral Fibre ceiling tiles of Meter or equivalent finish tile Tegular edge laid on grid of colour white as per entire satisfaction and direction of Engineer-in-charge.</p>	126.25	sqm			
	<b>Total</b>					

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-  
Superintending Engineer