

No. IITMandi(CW)/SE-1243/2021-22/6624-25

Dated:22/02/2022

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **02/03/2022 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Name of work: Construction of kitchen shelve in Cafeteria at A-19 block in North Campus of IIT Mandi, H.P.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **10 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of Work:-Construction of kitchen shelve in Cafeteria at A-19 block in North Campus of IIT Mandi, H.P.

Sr. no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) as per entire satisfaction and direction of Engineer-in- charge.	0.97	cum			
2	Centering and shuttering including strutting, propping etc. and removal of form for :Shelves (Cast in situ) as per entire satisfaction and direction of Engineer-in- charge.	6.48	sqm			
3	Edges of slabs and breaks in floors and walls Under 20 cm wide as per entire satisfaction and direction of Engineer-in- charge.	10.80	mtr.			
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more as per entire satisfaction and direction of Engineer-in- charge.	67.90	Kg			
5	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite stone slab colour black, Cherry/Ruby red Area of slab over 0.50 sqm as per entire satisfaction and direction of Engineer-in- charge.	7.20	sqm			
6	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete Granite work as per entire satisfaction and direction of Engineer-in-charge.	12.00	mtr.			

Sr.no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) as per entire satisfaction and direction of Engineer-in- charge.	0.44	cum			
8	CEMENT PLASTER (IN FINE SAND) 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand) as per entire satisfaction and direction of Engineer-in- charge.	3.84	sqm			
9	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete as per entire satisfaction and direction of Engineer-in- charge.	3.84	sqm			
10	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :New work (two or more coats) over and including water thinnable priming coat with cement primer as per entire satisfaction and direction of Engineer-in- charge.	3.84	sqm			
Total						

- Note :-
1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).
 2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer