

No. IITMandi(CW)/SE-1268/2022-23/1485-86

Dated:12/05/2022

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby re-invited by the undersigned from registered contractors so as to reach in this office on or before **19/05/2022 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand South campus in the presence of intending contractors or their authorized representatives.

Name of work: Providing and fixing of collapsible steel gate at Mumty of A-17 & A18 block of North campus.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **10 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of Work:-Providing and fixing of collapsible steel gate at Mumty of A-17 & A18 block of North campus.

Sr.no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing:1:1½:3 (1 cement : 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) as per entire satisfaction and direction of Engineer-in- charge.	0.16	Cum			
2	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. as per entire satisfaction and direction of Engineer-in- charge.	382.16	Kg			
3	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer as per entire satisfaction and direction of Engineer-in- charge.	15.00	sqm			
4	CEMENT PLASTER (IN FINE SAND) 12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand) as per entire satisfaction and direction of Engineer-in- charge.	0.81	Sqm			
5	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade :New work (two or more coats) over and including water thinnable priming coat with cement primer .as per entire satisfaction and direction of Engineer-in- charge.	1.00	Sqm			
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work as per entire satisfaction and direction of Engineer-in- charge.	25.12	Sqm			
7	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	0.16	cum			
Total						

- Note :-
1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).
 2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer