

No. IITMandi(CW)/SE-1282/2022-23/2757-58

Dated:15/07/2022

**NOTICE INVITING QUOTATION**

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **22/07/2022 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand South campus in the presence of intending contractors or their authorized representatives.

**Name of work: Providing and fixing of precoated galvanized sheet of corridor of clean room A-4 at South Campus.**

----- As Per Schedule Attached -----

**Terms & Conditions:-**

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **30 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Contractor shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-  
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-  
Superintending Engineer

## Schedule of Quantity

Name of Work:-Providing and fixing of precoated galvanized sheet of cooridor of clean room A-4 at South Campus

Sr.no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) as per entire satisfaction and direction of Engineer-in-charge.	3.20	cum			
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns as per entire satisfaction and direction of Engineer-in- charge.	3.20	sqm			
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per entire satisfaction and direction of Engineer-in- charge.	235.40	kg			
4	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer- in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required as per entire satisfaction and direction of Engineer-in- charge.	108.80	sqm			
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work as per entire satisfaction and direction of Engineer-in- charge.	12.01	sqm			
6	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet as per entire satisfaction and direction of Engineer-in- charge.	108.80	sqm			
<b>Total</b>						

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).  
2. All Statutory deduction will be made as per prevailing rates.

Sd/-  
Superintending Engineer