

No. IITMandi(CW)/SE-1289/2022-23/3464-65

Dated:18/08/2022

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **26/08/2022 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Name of work: Repair & Re-painting on wall & Ceiling of Bamboo A, B & C in South Campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **21 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of Work: Repair & Re-painting on wall & Ceiling of BambooA, B & C in South Campus of IIT Mandi.

Sr. No.	Description of Item	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Providing and fixing plain multipurpose cement board(Hight pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seperatately). 6 mm thick Cement fiber board as per IS: 14862 as per entire satisfaction and direction of Engineer -in-charge including carriage of material within all lead and lift.	29.28	sqm			
2	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer- in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required as per entire satisfaction and direction of Engineer -in-charge including carriage of material within all lead and lift.	18.30	sqm			
3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work as per entire satisfaction and direction of Engineer -in-charge including carriage of material within all lead and lift.	29.28	sqm			
4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture as per entire satisfaction and direction of Engineer -in-charge including carriage of material within all lead and lift.	84.97	sqm			

5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work as per entire satisfaction and direction of Engineer -in-charge including carriage of material within all lead and lift.	703.80	sqm			
6	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (One or more coat applied @ 0.90 ltr/10 sqm) as per entire satisfaction and direction of Engineer -in-charge including carriage of material within all lead and lift.	882.63	sqm			
7	Providing and fixing brass curtain rods of wall thickness 1.25 mm with two brass brackets fixed with brass screws and wooden plugs etc. wherever necessary complete. 25 mm diameter as per entire satisfaction and direction of Engineer -in-charge including carriage of material within all lead and lift.	40.50	metre			
Total						

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer