

No. IITMandi(CW)/SE-1417/2023-24/1417

Dated:04/07/2023

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **12/07/2022up to 03:00 PM** and shall be opened on the same day at **03:30PM** in the O/o Superintending Engineer, IIT Mandi at Kamand South campus in the presence of intending contractors or their authorized representatives.

Name of work:Preparation of lawn and laying of selection no. 1 grass at lawn near animal house and B-8 & B-9 at South Campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil and horticultural Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **28 days** from issue of work order.
3. Anydamages done during execution of the work/repairs are to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Contractor shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of Work:-Preparation of lawn and laying of selection no.1 grass at lawn near animal house and B-8 & B-9 at South campus of IIT Mandi.

Sr. No.	Description of Item	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Uprooting rank vegetation and weeds by digging the area to a depth of 60cm, removing all weeds and other growth with roots byforking repeatedly,breaking clods, rough dressing, flooding withwater, uprooting fresh growthsafter 10 to 15 days and then finedressing for planting new grass,includingdisposal of all rubbishwith all leads and lifts as per entire satisfaction and direction of Engineer-in-charge.	1640.00	sqm			
2	Supplying and stacking of good earth at site including royalty and carriage upto 5 km lead complete (earth measured in stacks will be reduced by20% for payment) as per entire satisfaction and direction of Engineer-in-charge.	65.00	cum			
3	Spreading of sludge, dump manure and/or good earth in required thicknessas per direction of officer-in-charge (cost of sludge, dump manure and/ orgood earth to be paid separately) as per entire satisfaction and direction of Engineer-in-charge.	65	cum			
4	Supplying and spreading of sand in lawn area, including watering, and dressing complete as per entire satisfaction and direction of Engineer-in-charge.	10	cum			
5	Supplying and stacking at site compost weed free from approved source including carriage at site as per entire satisfaction and direction of Engineer-in-charge.	1000	Kg			
6	Grassing with selection No. 1 Doob grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the grass and good earth shall be paid for separately) in rows 5 cm apart in both directions as per entire satisfaction and direction of Engineer-in-charge.	1640	sqm			

Sd/-
Superintending Engineer