

No. IITMandi(CW)/SE-1418/2023-24/1622-23

dated:04-07-2023

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **12/07/2023 up to 03:00 PM** and shall be opened on the same day at **03:30PM** in the O/o Superintending Engineer, IIT Mandi at Kamand South campus in the presence of intending contractors or their authorized representatives.

Name of work:-Construction of concrete path for newly constructed S.T.P. at South campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **28 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of work:- Construction of concrete path for newly constructed S.T.P. at South campus of IIT Mandi.

Sr. No.	Description of Item	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, All kinds of soil as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	81.90	sqm			
2	Dry stone pitching 22.5 cm thick including supply of stones and preparing surface complete as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	81.90	sqm			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	8.19	cum			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	8.19	cum			
5	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	36.40	sqm			
Total						

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST (nothing extra shall be payable).
2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer