

No. IITMandi(CW)/SE-1426/2023-24/1580-81

Dated:04/07/2023

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **10/07/2022 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand South campus in the presence of intending contractors or their authorized representatives.

Name of work: Providing and fixing of GI fencing panel for protection from monkey in B8 & B9 hostel at South Campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **21 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Contractor shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of work:-Providing and fixing of GI fencing panel for protection from monkey in B8 & B9 hostel at South Campus of IIT Mandi.

Item no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	462.72	Kg			
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	30.60	Sqm			
3	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	151.00	Sqm			
Total						

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer