

No. IITMandi(CW)/SE-1451/2023-24/2491-92

Dated:21/07/2023

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **28/07/2023 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Name of work:-Repainting and repairing of Chandra Taal Hostel at South Campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **21 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of work:-Repainting and repairing of Chandra Taal Hostel at South Campus of IIT Mandi.

Item no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	54.37	sqm			
2	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	56.64	sqm			
3	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. One coat per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1471.76	sqm			
4	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand) per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	133.42	sqm			
Total						

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer