Indian Institute of Technology Mandi Mandi, Himachal Pradesh - 175075



भारतीय प्रौद्योगिकी संस्थान मंडी मंडी, हिमाचल प्रदेश - 175075

IITMandi(CW)/SE-1480/2023-24/4036-37

Dated:03/10/2023

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before 11/10/2023 up to 03:00 PM and shall be opened on the same day at 03:30 PM in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

<u>Name</u>	of	work:-	Providing	&	fixing	power	poin [.]	ts to	HPC	racks	in	A9	bui	lding
			Supercomp Mandi.	uteı	r Paran	n Himo	alaya	Room	at	South	Cam	pus	of	IIT
			As	Per	Schedu	ıle Atto	iched							

Terms & Conditions: -

- 1. The work will be carried out as per CPWD General Specifications for **Electrical** works amended up to date & as per the instructions of the Engineer-in-charge.
- 2. The work is to be completed within 21 days from issue of work order.
- 3. All damages done during execution of the work is to be made good by the agency and nothing extra will be paid separately for the same.
- 4. The Prices quoted should be net and nothing extra is to be paid.
- 5. Contractor shall abide by labour rules and regulations.
- 6. All the applicable taxes shall be deducted from the bill.
- 7. Compensation of delay of work will be @ 0.05% per day.
- 8. GST Registration Certificate should also be attached with NIQ.
- 9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
- 10. All material to be used on the work will have to be got approved from the Engineer-in-charge

Sd/-Superintending Engineer

Copy to:-

- 1. Notice Board.
- 2. Institute Website

Sd/-Superintending Engineer

Schedule of Quantity

Name of Work:-Providing & fixing power points to HPC racks in A9 building Supercomputer Param Himalaya Room at South Campus of IIT Mandi.

Sr. no.	Nessuinitien of item	Qty	Unit		Rate(In Rs)	Amount	
	Descripition of item		Unit	(In Figure)	(In Word)	(In Rs)	
1	Supplying and fixing 15/16 A switch modular switch on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	48	Each				
2	Supplying and fixing 6 pin 15/16 A socket outlet modular socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and	48	Each				
3	Supplying and fixing Single pole 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of Single pole, in the existing MCB DB complete with connections, testing and commissioning etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	24	Each				
4	Supplying and fixing 6 Module, PVC box alongwith modular base & cover plate for modular switches in recess etc as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	24	Each				
5	Supplying and drawing 3 Core 6 Sq. mm PVC insulated Multistrand copper cable in the existing surface/recessed steel/ PVC conduit / PVC Casing as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	150	Meter				
6	Supplying and fixing of 50 mm size of Heavy Duty PVC Casing Caping Double lock along with accessories in surface as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	30	Meter				
	Total						

Note:- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).
2. All Statutory deduction will be made as per prevailing rates.

Sd/-

Superintending Engineer