Indian Institute of Technology Mandi Mandi, Himachal Pradesh - 175075



भारतीय प्रौद्योगिकी संस्थान मंडी मंडी, हिमाचल प्रदेश - 175075

सं0: आई0 आई0 टी0 मण्डी/सी डब्ल्यू/ एस ई-1613/2024-25/510-11

दिनांक 11/06/2024

# NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **20/06/2024 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

# Name of work: Providing and fixing of aluminium partition in the ED lab (A18.00.02) at North campus of IIT Mandi.

----- As Per Schedule Attached -----

## Terms & Conditions:-

- 1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
- 2. The work is to be completed within 20 days from issue of work order.
- 3. Anydamages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
- 4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
- 5. Agency shall abide by labor rules and regulations.
- 6. All the applicable taxes shall be deducted from the bill.
- 7. Compensation of delay of work will be @ 0.05% per day.
- 8. GST Registration Certificate should also be attached with NIQ.
- 9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
- 10. All material to be used on the work will have to be got approved from the Engineer-incharge.

Sd/-Superintending Engineer अधीक्षण अभियंता

Copy to:-

- 1. Notice Board, IIT Mandi.
- 2. Institute Website, IIT Mandi.

Sd/-Superintending Engineer अधीक्षण अभियंता

### Schedule of Quantity

#### Name of work :Providing and fixing of aluminium partition in the ED lab (A18.00.02) at North campus of IIT Mandi.

Sr. No.	Description of Item	Qty.	Unit		<b>A</b>	
				(T., Dimme)	Rate(In Rs)	Amount (In Rs)
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : a)For fixed portion i)Powder coated aluminium (minimum thickness of powder coating 50 micron)		Kg	(In Figure)	(In Word)	
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : b) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately). i) Powder coated aluminium (minimum thickness of powder coating 50 micron)		Kg			
ŀ	Providing and fixing 12mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 Grade 1 Type ll, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. a) Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side.		Sqm			
5	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): a) With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)		Sqm			
ò	Providing and fixing Brass 100mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete.		No.			
7	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/neoprene gasket etc .complete as per the architectural drawings and the directions of Engineer-in-Charge.(Cost of aluminium snap beading shall be paid in basic item): With frost glass panes of 5.00 mm thickness complete as per architectural drawings and directions of Engineer-in-charge.		Sqm			

Sr.	Description of Item	Qty.	Unit	Rate(In Rs)		Amount
No.				(In Figure)	(In Word)	(In Rs)
	Providing and fixing Powder coated aluminium handles, ISI marked, (minimum thickness of powder coating 50 micron) with necessary screws etc. 200mm complete as directed by Engineer-in- charge.		No.			
	Providing and fixing Roller set for Sliding door, ISI marked, with necessary screws etc. complete as directed by Engineer-in-charge.	1.00	No.			
	Total					

Note : 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-Superintending Engineer