



No. IITMandi(CW)/SE-1462/2023-24/3050-51

dated:25-08-2023

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **01/09/2023 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand South campus in the presence of intending contractors or their authorized representatives.

Name of work: Providing and Laying of Kota stone in ground floor, S.S. railing for staircase of A-09 building at North Campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **20 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of work: Providing and Laying of Kota stone in ground floor, S.S. railing for staircase of A-09 building at North Campus of IIT Mandi.

Sr. No.	Description of Item	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) all complete as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	1.43	sqm			
2	Centering and shuttering including strutting, propping etc. and removal of form work for :Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. all complete as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	19.00	Sqm			
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works all complete as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	301.00	kg			
4	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :25 mm thick complete as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	22.80	sqm			
5	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing all complete as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	3.80	sqm			
6	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.) all complete as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	110.00	kg			
Total						

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer