

No: IIT Mandi (CW)/SE-1028/2018-19/12206-07

Date: 08/03/2019

## NOTICE INVITING QUOTATION

Quotation for the work "Construction of Covered path for Hostel block B-05 and G-04 at kamand campus of IIT Mandi." as per schedule attached is hereby invited by the undersigned from registered contractors of appropriate class which shall be handed over to members of works/purchase committee on or before **14-03-2019 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractor or their authorized representatives.

### Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed within **15 days** from issue of work order.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-

OSD

Construction & Maintenance Wing

Copy To:-

1. Notice board.
2. Institute Website.

Sd/-

OSD

Construction & Maintenance Wing

## Schedule of Quantity

**Name of work :** -Construction of Covered path for Hostel block B-05 and G-04 at kamand campus of IIT Mandi.

Sr. No.	Description of items	Qty	Unit	Rates (In Rs.)		Amount (In Rs.)
				(In Figures)	(In Words)	
1	Surface dressing of the ground including removing vegetation and in- equalities not exceeding 15 cm deep and disposal of rubbish in all lead and lift all kinds of soil as per entire satisfaction and direction of engineer -in -charge.	9.80	sqm			
2	Excavating holes more than 0.10 cum & upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc, disposing of surplus excavated soil, as directed within in all lead and lift all kinds of soil as per entire satisfaction and direction of engineer -in -charge.	20.00	each			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size) as per entire satisfaction and direction of engineer -in -charge.	2.57	cum			
4	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.Nominal concrete 1:3:6 or richer mix (i/c equivalent mix) as per entire satisfaction and direction of engineer -in -charge.	0.48	cum			
5	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes as per entire satisfaction and direction of engineer -in -charge.	925.11	kg			
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work as per entire satisfaction and direction of engineer -in -charge.	37.53	sqm			

7	Providing & fixing UV stabilised fiberglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigs incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified. 2 mm thick flat as per entire satisfaction and direction of engineer -in -charge.	38.53	sqm			
8	Providing and laying 40mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per entire satisfaction and direction of engineer -in -charge.	9.80	sqm			
Total						

- Note :-
1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).
  2. All Statutory deduction will be made as per prevailing rates.

Sd/-  
OSD  
Construction & Maintenance Wing