

NOTICE INVITING QUOTATION

Quotations for the work "**Conversion of the parking shed adjacent to Recreation Centre into electrical 3 wheelers stand at South Campus of IIT Mandi**", as per schedule attached is hereby invited by the undersigned from registered contractors up to **10-12-2020 by 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **civil works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed within **30 days** after issue of work order.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. Compensation of delay of work will @ 0.05% per day on account of non-completion of work within stipulated period.
8. All material to be used on the work will have to be got approved from the Engineer-in-charge.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. GST Registration Certificate should also be attached with NIQ.

Sd/-
Superintending Engineer

Copy to:-

1. Notice board.
2. Institute website

Sd/-
Superintending Engineer

SCHEDULE OF QUANTITY

Name of work:- Conversion of the parking shed adjacent to recreation centre into electrical 3 wheelers stand at South campus of IIT Mandi.

| S.No | Description | Qty. | Unit | Rate(In Rs) | | Amount (In Rs) |
|------|---|--------|-------|-------------|-----------|-------------------|
| | | | | (In Figure) | (In Word) | |
| 1 | Excavating holes more than 0.10 cum & upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc, disposing of surplus excavated soil, as directed within a lead of 50 m and lift upto 1.5 m. All kinds of soil as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts. | 6.00 | each | | | |
| 2 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts. | 3.65 | cum | | | |
| 3 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts. | 0.12 | cum | | | |
| 4 | Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts. | 2.16 | sqm | | | |
| 5 | Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in : cement mortar 1:4 (1 cement : 4 coarse sand) as per entire satisfaction and direction of Engineer-in-charge | 9.50 | sqm | | | |
| 6 | Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per entire satisfaction and direction of Engineer-in-charge | 225.45 | kg | | | |
| 7 | Providing and fixing glass strips in joints of terrazo/ cement concrete floors. 40 mm wide and 4 mm thick as per entire satisfaction and direction of Engineer-in-charge | 43.20 | metre | | | |
| 8 | 15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement: 6 coarse sand) as per entire satisfaction and direction of Engineer-in-charge | 19.00 | sqm | | | |
| 9 | Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) as per entire satisfaction and direction of Engineer-in-charge | 19.00 | sqm | | | |

| S.No | Description | Qty. | Unit | Rate(In Rs) | | Amount (In Rs) |
|--------------|--|-------|------|-------------|-----------|-------------------|
| | | | | (In Figure) | (In Word) | |
| 10 | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work as per entire satisfaction and direction of Engineer-in-charge | 10.02 | sqm | | | |
| 11 | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix) as per entire satisfaction and direction of Engineer-in-charge | 0.04 | cum | | | |
| 12 | Design, Supply, fabrication & Installation of roof for different shape consisting of single skin minimum 6.00mm thick polycarbonate transparent sheet, UV stablized, properly jointed and fixed with M.S.frame,fasteners,gutters,gaskets, sealants and necessary structural supports as required as per approved drawings and specifications.The work includes preparation of shop drawings as per manufacturer's specifications and approved architectural drawings complete etc. which shall be approved by Engineer-in-charge.(M.S. frame work shall be paid seperately) as per entire satisfaction and direction of Engineer-in-charge | 28.50 | sqm | | | |
| TOTAL | | | | | | |

- Note :: 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).
2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer