

IITMandi(CW)/SE-1255/2022-23/ 1225-26

Dated: 05/05/2022

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **12/05/2022 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Name of work: - Providing and fixing power points on the computer tables at the PC Lab in A11 block of North Campus.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Electrical works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **20 days** from issue of work order.
3. All damages done during execution of the work is to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of Work:- Providing and fixing power points on the computer tables at the PC Lab in A11 block of North Campus.

Item no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Supplying and drawing 3x4 sq mm of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/ PVC conduit/Flexible Pipe/Race Way as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	330	Meter			
2	Supplying and fixing 5/6 A switch modular switch on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	180	Each			
3	Supplying and fixing 3 pin 5/6 A socket outlet modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	180	Each			
4	Supplying and fixing 6 Module Modular base & cover plate on existing modular metal boxes etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	90	Each			
5	Supplying and fixing of 20 mm size of medium class PVC Flexible Pipe along with accessories in surface as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	135	Meter			
6	Supplying and fixing 6 Modue PVC box to be fixed in open surface/Wall as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	90	Each			
7	Connections and testing of Existing miniature circuit breaker suitable for inductive load of 5 amps to 32 amps rating, 240/415 volts, 10 kA, "C" curve, Single poles in the existing MCB DB complete with connections, testing and commissioning etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	25	Each			
Total						

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer