



No: IIT Mandi (CW)SE-1074/2019-20/9999-10000

Date:05/11/2019

NOTICE INVITING QUOTATION

Quotation for the work "Re-strengthening of cooling tower Slab at AHU building at South Campus of IIT Mandi." as per schedule attached is hereby invited by the undersigned from registered contractors/Firms which shall be handed over to members of works/purchase committee on or before **13/11/2019 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Construction Wing, IIT Mandi at Kamand campus in the presence of intending contractor or their authorized representatives.

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed within **30 days** from issue of work order.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-

Superintending Engineer

Copy To:-

1. Notice board.
2. Institute Website.

Sd/-

Superintending Engineer

Schedule of Quantity

Name of work : -Re-strengthening of cooling tower Slab at AHU building at South Campus of IIT Mandi.

Sr. No.	Description of items	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figures)	(In Word)	
1	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge (Note :- Cement content considered in this item is @ 330 kg/cum. Excess/ less cement used as per design mix is payable/recoverable separately). All works above plinth level upto floor V level as per entire satisfaction and direction of engineer-in-charge	10.68	cum			
2	Centering and shuttering including strutting, propping etc. and removal of form for : Edges of slabs and breaks in floors and walls Under 20 cm wide as per entire satisfaction and direction of engineer-in-charge	43.60	mtr.			
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.Thermo-Mechanically Treated bars of grade Fe-500D or more as per entire satisfaction and direction of engineer-in-charge	143.34	kg			
4	Add/Less for using extra/less cement in the items of design mix over and above the specified cement content therein as per entire satisfaction and direction of engineer-in-charge	7.48	quintal			
5	Providing and applying fibre reinforced elastomeric liquid water proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge.	118.72	sqm			
				Total		

- Note :-
1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).
 2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer