Indian Institute of Technology Mandi Mandi, Himachal Pradesh - 175075



भारतीय प्रौद्योगिकी संस्थान मंडी मंडी, हिमाचल प्रदेश - 175075

No. IITMandi(CW)/SE-1470/2023-24/3310-11

Dated:04-09-2023

## NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before 12/09/2023 up to 03:00 PM and shall be opened on the same day at 03:30 PM in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

<u>Name of work</u>: -Supply and fixing of LED Bollard Light on pathway approaching the park in front of C14 building at North Campus of IIT Mandi.

----- As Per Schedule Attached -----

## <u>Terms & Conditions:-</u>

- 1. The work will be carried out as per CPWD General Specifications for **Electrical** works amended up to date & as per the instructions of the Engineer-in-charge.
- 2. The work is to be completed within **30 days** from issue of work order.
- 3. All damages done during execution of the work is to be made good by the agency and nothing extra will be paid separately for the same.
- 4. The Prices quoted should be net and nothing extra is to be paid.
- 5. Contractor shall abide by labour rules and regulations.
- 6. All the applicable taxes shall be deducted from the bill.
- 7. Compensation of delay of work will be @ 0.05% per day.
- 8. GST Registration Certificate should also be attached with NIQ.
- 9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
- 10. All material to be used on the work will have to be got approved from the Engineerin-charge

Sd/-Superintending Engineer

Copy to:-

- 1. Notice Board.
- 2. Institute Website

Sd/-Superintending Engineer

## Schedule of Quantity

## Name of Work:- Supply and fixing of LED Bollard Light on pathway approaching the park in front of C14 building at North Campus of iiT Mandi.

Item no	Descripition of item	Qty	Unit	Rate(In Rs)		Amount
				(In Figure)	(In Word)	(In Rs)
1	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of	120.00	Meter			
	upto 35 sq. mm direct in ground including excavation, sand cushioning, protective covering and					
	refilling the trench etc as required as per entire satisfaction and direction of Engineer-in-charge					
	including carriage of material in all leads and lifts.					
2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost	1.51	Cum			
	of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1					
	cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20					
	mm nominal size de rived from natural sources) as per entire satisfaction and direction of					
	Engineer-in-charge including carriage of material in all leads and lifts.					
3	Supplying and making end termination with brass compression gland and aluminium lugs for 4 X	4.00	Each			
	16 sq.mm ( 28 mm) (Inside LT Panel) size of PVC insulated and PVC sheathed / XLPE aluminium					
	conductor cable of 1.1 KV grade as required as per entire satisfaction and direction of Engineer-in-					
	charge including carriage of material in all leads and lifts.					
	Supplying and drawing 3X1.5 sq. mm of FRLS PVC insulated copper conductor, single core cable in	38.00	Meter			
4	the existing surface/recessed steel/PVC conduit as per entire satisfaction of the engineer					
	incharge including carriage pf materil in all leads and lifts.					
5	Supplying and installtion of LED bollard of 9W with opal acryllic diffuser and IP 66 protection , CCT	14.00	Each			
	5700 k etc. as per entire satisfaction and direction of Engineer-in-charge including carriage of					
	material in all leads and lifts.					
6	Supplying of 4 Core x 16 Sq. mm of 1.1 KV Aluminium conductor XLPE Insulated, PVC extruded	120.00	Meter			
	inner-sheathed, round wired GI strip armoured, overall PVC outer-sheathed (as per IS 7098 Part					
	1) with latest amendments as required as per entire satisfaction and direction of Engineer-in-					
	charge including carriage of material in all leads and lifts.					
	Total					

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.